



CCAT-prime Overview and Update

Terry Herter (Project Director) for the CCAT-Team


1st CCAT Collaboration Meeting

07-Apr-2020

CCAT-prime Observatory

- What is it?
 - 6-m telescope design for wide-area surveys (large FoV)
 - located in high Atacama Desert of N. Chile (high trans., low ϵ)
 - Designed to address broad science questions
 - Expected first light late 2021/early 2022
- CCAT studies will range from
 - mapping of gas and dust in the Milky Way to
 - the formation of the first galaxies to
 - probing the CMB for information on new particle species, the formation of cluster of galaxies and as a lead in to CMB-S4
 - among others to be discussed here
- Links to CCAT publications: <http://www.ccatobservatory.org/>
 - See reports & publications under documents link
 - Astro2020 White paper on CCAT-prime with links to white papers on science themes/topics
 - Technical papers on telescope, instrumentation, etc.


Extragalactic Survey Areas



Survey fields overlaid on Planck dust map

(1) Deep Subaru HSC+PSF spectroscopy (current) & COSMOS X-Ray-to-meter-wave multiwavelength survey; (2) deep Euclid grism spectroscopy (upcoming), HERA HI 21 cm (upcoming), & H-UDF/CDF-S multiwavelength surveys (incl. JWST GTO); (3) HERA HI 21 cm (upcoming), VLASS; (4) Planck, SDSS, DES, ACT (current), SO, DESI, LSST, eROSITA (upcoming).

The 6-m CCAT-prime telescope




- Aperture: 6-m
- Large FoV: $\sim 7.3^\circ \cdot (\lambda/3 \text{ mm})^{1/2}$
- HWFE: $< 11 \mu\text{m}$
 - Half wave-front error
 - Redundant checks: laser metrology system and near-field holography
- Pointing Error: $< 1.4''$
- Low emissivity: $< 2.8\%$ (goal $< 1\%$)
- Scan patterns: azimuthal
 - Typically azimuthal scans, but accelerations adequate for other patterns
- Scan speed: $> 0.33^\circ \text{ s}^{-1} \cdot (\lambda / 350 \mu\text{m})$
 - in azimuth, and half this value in elevation
- Stray light mitigations
 - Option to add baffles

- CCAT-prime optical layout
 - See Niemack 2016, Parshley, 2018
- Ray trace shows sources -2, 0, and 2 degrees off-axis
- Locations of instrument spaces 1 and 2 are shown (IS-1, IS-2)

Status

- Telescope under construction
- Site Preparation
 - Upgraded road nearly complete: 5-month hiatus then 1 month to finish
 - One month for site leveling after road complete
 - Foundation installation on track (Apr 2021)
- Instrumentation
 - CHAI: on schedule
 - Prime-CAM:
 - 1-tube Mod-Cam cryostat for first-light (270 GHz)
 - 7-tube Prime-Cam cryostat in fabrication

Telescope




Anchor Ring



- Above: Delivery to Vertex
- Left: Loading SOLAT anchor ring for shipment

Telescope Foundation




- Vital Stats:

- 14m diameter x ~3m tall: 13 pre-cast pieces: 1 hub = 14t, 12 radials = 27t each
- ~ 70 cubic meters of in situ concrete to "glue" pre-cast pieces together and embed telescope anchor ring
- ~ 12 km of rebar total in the foundation (joints contain rebar)
- total mass ~ 500t, additional ~ 450t of backfill on top
- supports ~ 220t telescope, reacts against ~ 200t moving in AZ

TAO Foundation



Telescope Structure



VERTEX ANTENNENTECHNIK GmbH
A GENERAL DYNAMICS COMPANY

NOTE: THIS DOCUMENT CONTAINS PROPRIETARY INFORMATION AND MAY NOT BE DISCLOSED WITHOUT THE WRITTEN CONSENT OF VERTEX ANTENNENTECHNIK GmbH - Duisburg

Telescope Support Cone



Steel support cone in manufacture. Finished cone will be ~ 8 tons.

Wessel



Beginning of Yoke Traverse




Elevation Drive Bearing



- CCAT elevation drive gear




Mirror Panel




- Left: Front side of CCAT-Prime 0.7-m mirror panel. The surface RMS is approximately 2 microns.
- Right: Back side of mirror panel showing light-weighted structure, the five mounting points for attachment to the carbon fiber backing structure, and recesses for the x-y adjustment (along horizontal line in center).

Instrumentation


Name	Primary Science	λ range	FoV	No. Pixels	1 st Light?
CHAI	GEco	200 – 700 μm	17' x 8.5'	128 (256 goal)	yes
P-Cam	kSZ, GEvo	350 – 1300 μm	3 $^\circ$ diameter	5.9×10^4	yes
P-Cam	IM/EOR	740 – 1300 μm	--	2.0×10^4	yes
CMB-S4	CMB	350 – 3100 μm	7.8 $^\circ$ diameter	1.5×10^5	no




CHAI



Prime-Cam




CCAT Location



CCAT Site

- The low precipitable water vapor (PWV) at the CCAT site offer advantages over the ALMA plateau (5500 vs. 5000 m).
- For an equivalent setup, Cerro Chajnantor is better at all wavelengths.



Road Improvements




Road Improvements




Road Improvements







Schedule



Now

Acceptance Testing & Commissioning

- FDR / Post-FDR
 - Verification of ~150 requirements by design and analysis - ongoing
- Factory acceptance testing (FAT, pre-assembly in Germany)
 - Verification of ~40 requirements by measurement
 - Functional tests (limits, stow pins, etc.)
- Site acceptance testing (SAT, final assembly on C. Chajnantor)
 - Verification of ~50 requirements by measurement
 - Functional tests redux
 - Closes out contract with Vertex
- Holography, Laser Metrology, and IR Pointing Camera are strongly desired for FAT and absolutely required for SAT
- Commissioning:
 - Post-SAT – further telescope refinement & characterization
 - Occurs for each instrument (I&T + Commissioning)
 - Combine some early science with commissioning activities



CCAT-p

2018 CCAT. All Rights Reserved. www.ccatobservatory.org

Scan Patterns

- Primary scan pattern for EoR IM, Cluster and CMB science is simply azimuthal:
 - Turn around time is ~ 2.5 s so, scanning at $\sim 1^\circ$ to $3^\circ/\text{sec} \Rightarrow >80\%$ efficiency for scans $> 10^\circ$ to 30°
 - EoR IM FoV is $\sim 16^{(\circ)^2}$, so 4° scan (@ $1^\circ/\text{s}$) would be only 62% efficient.
- Telescope performance will permit more sophisticated scan patterns, but not required

